

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-085-20072-00-00  
Spot: SENWSWSW Sec/Twnshp/Rge: 14-5S-15E  
810 feet from S Section Line, 510 feet from W Section Line  
Lease Name: ATWATER Well #: 13-14  
County: JACKSON Total Vertical Depth: 2390 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2370	667	180 SX CMT
SURF	8.625	235		120 SX CMT

\$ 77.68

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/23/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2323' TO 2231', CMT FROM 2231' TO 1944', GEL FROM 1944' TO 250', CMT FROM 250' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE  
Date/Time Plugging Completed: 01/25/2006 5:00 PM KCC Agent: TAYLOR HERMAN

**Actual Plugging Report:**

On 1-23-06 ran tubing and tagged bottom at 2274'. Pumped gel from 2274' to 2243'. Pulled tubing to 2243' and pumped 39 barrels of gel and 35 sacks of cement with 1 sack of cottonseed hulls. Had cement from 2243' to 1937' and gel from 1937' to 285'. Returned to the well on 1-25-06 and shot the 5.5" casing at 667'. Moved up to 312' and circulated 90 sacks of cement to surface and pulled the casing.

RECEIVED  
KCC DISTRICT #3

JUN 27 2006 TCH

CHANUTE, KS

**Perfs:**

Top	Bot	Thru	Comments
2178	2181		
2171	2173		
2148	2150		
2125	2128		
2099	2101		
2078	2080		
2052	2054		
1994	1996		

INVOICE  
DATE 7-10-06  
2007060017  
WELL NO 2007060017

Remarks:

Plugged through: TBG

District: 03

Signed

*Taylor C. Herman*

(TECHNICIAN)

RECEIVED  
JUL 05 2006  
KCC WICHITA

PET