

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-30402-00-01
Spot: NWSWSE Sec/Twnshp/Rge: 16-23S-14W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: WELSH/BEAVER TRACT 1 O Well #: 1-B
County: STAFFORD Total Vertical Depth: 4039 feet

Operator License No.: 31528
Op Name: KELSO, MIKE OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4038	1845	WITH 150 SX CMT
SURF	10.75	240		

\$ 131.27

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/21/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3500' & 5 SX CMT. PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 270' WITH 75 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/21/2006 3:45 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SAND TO 3500' THEN 5 SX CMT WITH DUMP BAILER. PUMP 15 SX GEL & 50 SX CMT AT 900'. CIRCULATED FLUID TO SURFACE. PUMP 75 SX CMT AT 270'. LOST CIRCULATION. WAIT 4 HOURS & TAG TBG AT 273'. PUMPED 5 SX GEL CIRCULATED TO SURFACE BUT FELL BACK. PUMP 6 SX GEL & CIRCULATED FLUID TO SURFACE. PUMP 75 SX CMT. CIRCULATE FLUID TO SURFACE. PUMP 25 SX CM AT 33'. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3976	3986		

RECEIVED
JUL 05 2006
KCC WICHITA


INVOICED

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID & CEMENT.

Plugged through: TBG

DATE 7-6-06
2007060021

District: 01



Signed

Jerry W. Stapleton
(TECHNICIAN)

PIRTE

Form CP-2

PCT