

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05158-00-00
Spot: S2NENW Sec/Twnshp/Rge: 11-15S-14W
4290 feet from S Section Line, 3300 feet from E Section Line
Lease Name: FLEGLER B Well #: 1
County: RUSSELL Total Vertical Depth: 3228 feet

Operator License No.: 31369
Op Name: GINTHER, KELLY DBA KAY DEE OIL
Address: 112 CINDY DR.
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3219	0	w/unknown sxs cmt
SURF	15	55	0	w/unknown sxs cmt

\$104.91

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/08/2006 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/08/2006 12:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Well had low fluid level.
Perforated at 1450'.
Pumped 150 sxs 60/40 pozmix - 10% gel cement down casing.
Max. P.S.I. 800#.
Perforated at 150'.
Tied onto casing and circulated up backside with 80 sxs cement.

INVOICED
DATE 7-6-06
REF. NO. 2007060016

RECEIVED
JUL 05 2006
KCC WICHITA

Remarks: QUALITY CEMENT.

Plugged through: CSG

District: 04

MD.

Signed _____

Case Morris

(TECHNICIAN)

JUN 28 2006

PCT

PRYOR & LOCKHART, INC #1 FLEGLER 'B' 11-15-14W
 CSL NE NW

Contr. _____ RUSSELL _____ County

E 1760 Comm. 7-30-43 Comp. 9-15-43 IP 825 BOPD

Tops	Depth	Datum
ANHY	765	
TOP	2654	
KIDGE	2902	
LANS	2970	
ARB	3214	
TD	3228	

Casing
 15" 55
 5" 3219
 SO & G 2325-32, 2440
 1 1/2 BOPH, 2905-15
 SFO PW 2976; SO & 1/2 BW 3168-70
 SFO 3214-19, HFW 3037-47
 Set Pkr @ 2995
 Perf 60/2968-80
 A/3000; Dual Comp.

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS