

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20574-00-00
Spot: SESWSE Sec/Twnshp/Rge: 31-18S-11W
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: KIMPLER Well #: 1
County: BARTON Total Vertical Depth: 3405 feet

Operator License No.: 31561
Op Name: HOFFMAN, CHRIS DBA C & K OIL COM
Address: 410 B STREET PO BOX 531
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3395	0	175 SX CMT
SURF	8.625	209	0	150 SX CMT

\$110.66

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2006 1:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: CHRIS HOFFMAN Company: C&K OIL COMPANY Phone: (620) 786-0644

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/09/2006 5:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran in with tubing. Hit several tight spots/bridges - stacked out at 1500'.
POOH. Ran in with perforating gun and could not get past 500'. Perfed at 500'.
Ran tubing to 1500' and pumped 110 sxs 60/40 pozmix - 10% gel cement.
Pulled to 800' and pumped 125 sxs cement.
Pulled to 400' and circulated with 40 sxs cement.
POOH. Tied onto backside and pumped 25 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.
Topped off with 15 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3395	3405		

INVOICED
7-6-06
2007060018
RECEIVED
JUL 05 2006
KCC WICHITA

Remarks: COPELAND CEMENTING COMPANY.

Plugged through: TBG

District: 04

10-

Signed Case Morris
(TECHNICIAN)

JUN 28 2006

PET

AL TIPTON #1 KIMPLER 31-18-11W
 IO LA, KS. SE SW SE
 CONTR LEBEN DRILLING, INC. CTY BARTON

GEOL J. C. MUSGROVE FIELD KIMPLER

E 1816 KB CM 4/5/71 CARD ISSUED 4/29/71 IP P 48 BOPD. N/W
 ARB 3395-3405



API 15-009-20,574
 SMP TOPS DEPTH DATUM 8 5/8" 209/150sx; 4 1/2" 3395/1

ANHY	636	+1180	DST(1) 3112-50/1', 10'M, BHP 427#
HEEB	2983	-1167	30", FP 17-17#
DOUG	3017	-1201	DST(2) 3395-3405/1', 60'GIP, 1200'GASSY
BN LM	3096	-1280	OIL (GR 40), BHP 838-813#, FP 83
LKC	3109	-1293	251#
ARB	3392	-1576	
RTD	3405	-1589	CO TO TD FU 2200'OIL/12HRS NAT., POP

MAILED

NO LOG

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS