

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21542-00-00
Spot: E2SENESE Sec/Twnshp/Rge: 34-13S-15W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: MAIE Well #: 1
County: RUSSELL Total Vertical Depth: 3326 feet

Operator License No.: 31250
Op Name: HUXMAN, RICHARD LEON DBA KSC O
Address: PO BOX 567
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3280		
PROD	5.5	3325	0	225 SX CMT
SURF	8.625	218	0	150 SX CMT

\$ 108.10

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/08/2006 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVE FUNK Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-3854

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/08/2006 5:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 2000'.
Pumped 100 sxs 60/40 pozmix - 10% gel cement w/500# hulls.
Pulled to 1000'.
Circulated with 80 sxs cement.
POOH. Pumped 50 sxs cement down backside.
Max. P.S.I. 400#. S.I.P. 200#.
Tied onto casing and pumped 30 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3325	3326		
3320	3325		
2880	2884		
2788	2795		

INVOICED

DATE 7-6-06
INVOICE NO. 2007060019

RECEIVED

JUL 05 2006

KCC WICHITA

Remarks: QUALITY CEMENT.

Plugged through: CSG

District: 04

HD -

Signed

Case Morris

(TECHNICIAN)

JUN 28 2006

PCT

