

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19036-00-00
Spot: NENENE Sec/Twnshp/Rge: 36-15S-14W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: DEINES Well #: 1
County: RUSSELL Total Vertical Depth: 3282 feet

Operator License No.: 32826
Op Name: MICHAELIS, ROGER DBA ALEO OIL CO
Address: 1864 NW 20 AVE.
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD 7		3290	0	w/unknown sxs cmt

106-67

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2006 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVE FUNK Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-3854

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2006 2:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Ran in with tubing and bit. Knocked through several bridges down to 1100' - hit steel - losing some fluid.
POOH. Ran in open ended to 1100' and pumped 100 sxs 60/40 pozmix - 10% gel cement with 400# hulls.
Pulled to 600' and circulated inside and out with 320 sxs cement and 300# hulls.
POOH. Topped off with 90 sxs cement. Stayed full.

INVOICED
JUL 7-6-06
2007060024
RECEIVED
JUL 05 2006
KCC WICHITA

Remarks: QUALITY CEMENT.

Plugged through: TBG

District: 04

10

Signed

Case Morris

(TECHNICIAN)

JUN 28 2006

PKT


CORALENA OIL CO #1 R DEINES 36-15-14W
NE NE NE

Contr. _____ RUSSELL _____ County

E 1853 Comm. 5-20-37 Comp. 6-10-37 IP 2699 BOPD

Tops	Depth	Datum
A-h. Top	824	+1029
Base	853	+1000
LKC	3034	-1181
ARB	3279	
TD	3282	

Casing
12" 484
8" 3279



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS