

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21978-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 9-14S-13W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HEINZE A Well #: 1
County: RUSSELL Total Vertical Depth: 2490 feet

Operator License No.: 4952
Op Name: SCHLOBOHM, STARR F.
Address: 10 GREENLEAF DRIVE
WOLFEBORO, NH 03894

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2479	0	60 SX
SURF	7	511	0	175 SX

\$ 80.93

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/12/2006 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOHN L. DRISCOLL Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-9580

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/12/2006 1:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 2330' and dumped 4 sxs cement.
Cut off casing at 1482'.
Pulled to 1425'.
Pumped 65 sxs 60/40 pozmix - 10% gel cement.
Pulled to 850' - pumped 30 sxs cement with 100# hulls.
Pulled to 200' and circulated with 20 sxs cement.

Perfs:

Top	Bot	Thru	Comments
2378	2383		W/2 SPF

INVOICE
DATE 7-6-06
2007060028

RECEIVED
JUL 05 2006

KCC WICHITA

Remarks: QUALITY CEMENT.

Plugged through: CSG

District: 04

jm

Signed

Case Morris

(TECHNICIAN)

JUN 28 2006

PKT

W 01250 W


A. SCOTT RITCHIE
125 N. MARKET, #950
WICHITA, KS. 67202
CONTR GLACIER DRILLING

REPLACEMENT CARD

#1 HEINZE 'A' 9-14-13W
NW SW SE

GEOL _____ CTY RUSSELL
FIELD HALL-GURNEY

ELV 1851 KB SPD 8/21/82 CARD 1846 GL ISSUED 1/6/83 IP P 2 BO & 112 BWPD
API 15-167-21,978 WAB(TARK SD) 2378-2383



SMP	Top	Depth/Datum
ANH		808 + 1043
B/ANH		841 + 1010
IND CV		2325- 474
GRDHAVEN		2368- 517
1ST TARK SD		2380- 529
2ND TARK SD		2399- 548
TARK LM		2437- 586
WILLARD SH		2455- 604
RTD		2490- 639

7" 511 / 175 SX, 4 1/2 " 2479 / 60 SX
NO CORES OR DSTS
MCT - CO, PF (TARK SD) 2378-2383, W / 2 SPF, AC 500 GAL
(15% MCA), FRAC 500 GAL GEL WTR & 150 SX SD, SOON, SWB
DWN & TSTD 15 BWPH / 4 HRS, ONFU 1400' FL, SWB DWN &
TSTD 15 BWPH / 6 HRS, SION, FU 1200' FL, T&R, POP, P 2 BO &
112 BWPD, 12/23/82
**CORRECTION & INFO RELEASED: 10/9/86 - ORIGINALLY FIRST
REPORTED AS #1 HEINZE, RPTD IN ERROR AS D & A 10/25/82 -
ADDED WELL INFO**