

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-20518-00-00
Spot: SWSESE Sec/Twnshp/Rge: 10-28S-6E
349 feet from S Section Line, 1065 feet from E Section Line
Lease Name: LUCAS D Well #: 2
County: BUTLER Total Vertical Depth: 3015 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION
Address: AZTEC OIL CO. DIVISION PO BOX 102
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3007		50 SX CMT
SURF	8.625	208		130 SX CMT

\$ 97.99

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2006 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: STEVEN W KILE Company: AZTEC OIL CO. Phone: (316) 322-5776

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 05/18/2006 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

4/19/2006 -- MIRU. Sanded back to 2955'. Dump bailed 6 sacks of cement on top.
4/21/2006 -- Shot 5-1/2" casing at 1200', 1105', and 625'. POOH with 625' of 5-1/2" casing.
5/18/2006 -- RIH with 1" to 260'. Braden Petroleum mixed and pumped 94 sacks of 60/40 posmix with 4% gel to surface.
Rig ticket #06-524
Cement ticket #06-528

Perfs:

Top	Bot	Thru	Comments
3007	3011		

**RECEIVED
KCC DISTRICT #2
JUN - 9 2006
WICHITA, KS**

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

PLUGGED
6-28-06
2006061861

RECEIVED
JUN 28 2006
KCC WICHITA

Form CP-2/3

PKT