

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-20530-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 11-28S-6E
339 feet from S Section Line, 5049 feet from E Section Line
Lease Name: LUCAS B Well #: 5
County: BUTLER Total Vertical Depth: 3015 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION
Address: AZTEC OIL CO. DIVISION PO BOX 102
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2997		75 SX CMT
SURF	8.625	204		140 SX CMT

\$97.99

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/10/2006 10:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Revd. from: STEVEN W KILE Company: AZTEC OIL CO. Phone: (316) 322-5776

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 05/03/2006 3:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

4/10/2006 -- MIRU.
4/11/2006 -- Laid down tubing and rods. Sanded back to 2945' and dump bailed 6 sacks of cement on top of sand.
4/12/2006 -- Shot 5-1/2" casing at 1425'. POOH with 1425' of 5-1/2" casing.
5/3/2006 -- RIH with 1" to 260'. Braden Petroleum mixed and pumped 90 sacks of 60/40 posmix with 4% gel to surface.
Rig ticket #06-521
Cement ticket #06-526

Perfs:

Top	Bot	Thru	Comments
2997	3014		
RECEIVED KCC DISTRICT #2 JUN - 9 2006 WICHITA, KS			

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

INVOICED
6-28-06
2006061861

RECEIVED
JUN 28 2006
KCC WICHITA

Form CP-2/3

n

PIC