

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20471-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 27-19S-1W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HAZEL M BANDY Well #: 1
County: MCPHERSON Total Vertical Depth: 3030 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3029		100 SX CMT
SURF	8.625	152		100 SX CMT

\$ 98.48

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/06/2006 8:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES CORPORAT Phone: (620) 654-7149

Proposed Plugging Method: Sand to 50' above perms and cap w/ 4 sxs cmt. Pump 35 sxs @ 430' and circ cmt from 250' to surf.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 02/06/2006 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 2860' and capped with 4 sacks of cement. Perforated casing at 450' and 250'. Ran 2" tubing to 450' and pumped 1-1/2 yds of slurry mix. Pulled tubing to 250' and pumped 6-1/2 yds of slurry mix and circulated to surface. Casing parted at 213' and was pulled.

8 yds of slurry mix
22 sxs per yd w/ 10% sand

McPherson Concrete Products #M34380

Perfs:

Top	Bot	Thru	Comments
2947	2948		

**RECEIVED
KCC DISTRICT #2
JUN - 5 2006
WICHITA, KS**

Remarks:

Plugged through: TBG

District: 02

Signed Greg Eves

(TECHNICIAN)

INVOICED
DATE 6-28-06
INSTR. NO. 2006061860

RECEIVED
JUN 28 2006
KCC WICHITA

Form CP-2/3

Handwritten mark

PKT