

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-21017-00-00  
Spot: SESENW Sec/Twnshp/Rge: 1-20S-1W  
2958 feet from S Section Line, 3088 feet from E Section Line  
Lease Name: BITIKOFER Well #: 1  
County: MCPHERSON Total Vertical Depth: 2926 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N. MARKET, STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2901		175 SX CMT
SURF	8.625	215		125 SX CMT

\$ 95.10

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/15/2006 12:00 PM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: Sand to 2860' and top w/ 5 sxs cmt. Pull csg. Run 2-5/8" tbg to 470' and spot 35 sxs cmt. Pull tbg to 270' and circ cmt to surf.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL  
Date/Time Plugging Completed: 02/15/2006 5:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

2/15/2006 -- Sanded well to 2860' and topped with 5 sacks of cement. Pulled 1368' of 5-1/2" casing. Ran 2-5/8" tubing to 470' and spotted 1 yd (33 sxs) of slurry mix. Pulled tubing to 270' and circulated 8 yds (176 sxs) of slurry mix to surface.  
2/20/2006 -- Topped of top plug with 1-1/2 yds (33 sxs) of slurry mix.  
Used slurry mix by McPherson Concrete Products #51914 & #51932.

Perfs:

Top	Bot	Thru	Comments
2901	2926		

RECEIVED  
KCC DISTRICT #2  
JUN - 6 2006  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

Michael Wilson

(TECHNICIAN)

INVOICED  
DATE 6-28-06  
2006061860

RECEIVED  
JUN 28 2006  
KCC WICHITA

Form CP-2/3

PRT