

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-21071-00-00  
Spot: S2S2NW Sec/Twnshp/Rge: 1-20S-1W  
2960 feet from S Section Line, 3858 feet from E Section Line  
Lease Name: BITIKOFER Well #: 3  
County: MCPHERSON Total Vertical Depth: 3020 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N. MARKET, STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2955		75 SX CMT
SURF	8.625	205		130 SX CMT

\$98.15

Well Type: SWD UIC Docket No: D23075.0 Date/Time to Plug: 02/20/2006 12:00 PM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Sand to 2905' and top with 5 sxs of cmt. Pull csg. Run 2-3/8" tbg to 450' and spot 35 sxs cmt. Pull tbg to 255' and circ cmt  
Plugging to surf.  
Method:

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL  
Date/Time Plugging Completed: 02/20/2006 5:00 PM KCC Agent: MICHAEL WILSON

**Actual Plugging Report:**

Sanded to 2750' and topped with 5 sacks of cement. Pulled 1080' of 5-1/2" casing. Ran 2-3/8" tubing to 450' and spotted 1 yd (33 sxs) of slurry mix. Pulled tubing to 270' and circulated 6 yds (132 sxs) of slurry mix to surface.

Used slurry mix by McPherson Concrete Products, Inc. #51931

9 yds of slurry mix  
22 sxs per yd w/ 10% sand

McPherson Concrete Products #M34481

**Perfs:**

Top	Bot	Thru	Comments
2955	3020		
RECEIVED KCC DISTRICT #2 JUN - 6 2006 WICHITA, KS			

Remarks:

Plugged through: TBG

District: 02

Signed Michael Wilson

(TECHNICIAN)

INVOICED  
6-28-06  
2006061860

RECEIVED  
JUN 28 2006  
KCC WICHITA

Form CP-2/3

PCT