

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19036-00-00
Spot: NWESW Sec/Twnshp/Rge: 11-28S-6E
2339 feet from S Section Line, 3754 feet from E Section Line
Lease Name: LUCAS B Well #: 2
County: BUTLER Total Vertical Depth: 3033 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION
Address: AZTEC OIL CO. DIVISION PO BOX 102
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3005		75 SX CMT
SURF	7	121		MUDDIED IN

\$ 98.57

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/27/2006 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: STEVEN W. KILE Company: AZTEC OIL CO. Phone: (316) 322-5776

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 05/26/2006 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

4/27/2006 -- MIRU. Laid out tubing and rods.
5/6/2006 -- 7" was loose in the hole.
5/11/2006 -- POOH with 120' of 7" casing.
5/23/2006 -- Shot off 5-1/2" casing at 910'. POOH with 3 jts (85'). RIH with 2-3/8" tubing at 935'. Braden Petroleum mixed and pumped 35 sacks of class A 2%. POOH with 2-3/8" tubing and 790' of 5-1/2" casing. Left 120' of 5-1/2" casing in hole for marker.
5/25/2006 -- RIH with 1" to 250'. Braden Petroleum mixed and pumped 145 sacks of 60/40 posmix with 4% gel.
5/26/2006 -- RIH with 1" to 140'. Braden Petroleum mixed and pumped 165 sacks of 60/40 posmix with 4% gel to surface.
Rig ticket #06-525
Cement ticket #06-530

Perfs:

Top	Bot	Thru	Comments
3005	3032		

RECEIVED
KCC DISTRICT #2
JUN - 9 2006
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

RECEIVED

JUN 28 2006

KCC WICHITA

INVOICED
6-28-06
2006061861

Form CP-2/3

M

PFT