

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-20369-00-00  
Spot: SESESE Sec/Twnshp/Rge: 10-28S-6E  
338 feet from S Section Line, 407 feet from E Section Line  
Lease Name: LUCAS D Well #: 1  
County: BUTLER Total Vertical Depth: 3015 feet

Operator License No.: 5387  
Op Name: THE BUCKEYE CORPORATION  
Address: AZTEC OIL CO. DIVISION PO BOX 102  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2987		100 SX CMT
SURF	8.625	202		90 SX CMT

\$ 97.99

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/18/2006 8:00 AM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C  
Proposal Revd. from: STEVEN W KILE Company: AZTEC OIL CO. Phone: (316) 322-5776

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/18/2006 2:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

4/18/2006 -- MIRU. Tubing hung up in hole.  
4/24/2006 -- Shot tubing at 2620'. POOH with 2620' of 2" tubing. Sanded back to 2610'.  
4/25/2006 -- Dump bailed 5 sacks of cement on top of sand.  
4/26/2006 -- Shot 5-1/2" casing at 1420'. POOH with 5-1/2" casing.  
5/18/2006 -- RIH with 1" tubing at 255'. Braden Petroleum mixed and pumped 92 sacks of 60/40 posmix with 4% gel to surface.  
Rig ticket #06-523  
Cement ticket #06-529

Perfs:

Top	Bot	Thru	Comments
2757	2760		
2749	2753		
2669	2673		

RECEIVED  
KCC DISTRICT #2  
JUN - 9 2006  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

*Duane Krueger*

(TECHNICIAN)

INVOICED  
DATE 6-28-06  
2006061861

RECEIVED  
JUN 28 2006  
KCC WICHITA

Form CP-2/3

PICT