

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21675-00-00
Spot: NENWSWNW Sec/Twnshp/Rge: 11-21S-7W
1483 feet from N Section Line, 362 feet from W Section Line
Lease Name: HAILE Well #: 1
County: RICE Total Vertical Depth: 3850 feet

Operator License No.: 33349
Op Name: LUDWICK, JOHN M. DBA JML COMPA
Address: 217 SOUTH 6TH ST.
STERLING, KS 67579

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3461		75 SX
SURF	8.625	221		165 SX

125.13

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/01/2006 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DOUG LOUIS WitnessType: PARTIAL
Date/Time Plugging Completed: 06/01/2006 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3310' and capped with 5 sacks of cement. Cut off casing at 2429'.
Pulled to 1050' and pumped 35 sacks of cement. Pulled casing to 600' and pumped 35 sacks of cement. Pulled casing to 270' and circulated cement to surface.

60/40 posmix with 4% gel

Copeland ticket #30523

Perfs:

Top	Bot	Thru	Comments
3360	3390		

RECEIVED
KCC DISTRICT #2
JUN - 9 2006
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED
6-28-06
2006061871

RECEIVED
JUN 28 2006
KCC WICHITA

Form CP-2/3

ACT