

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-00078-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 34-23S-5W  
4998 feet from S Section Line, 5078 feet from E Section Line  
Lease Name: STROUD Well #: 1  
County: RENO Total Vertical Depth: 3855 feet

Operator License No.: 32753  
Op Name: CARAGEANNIS, PAUL C. DBA SEED G  
Address: PO BOX 771189  
WICHITA, KS 67277

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD   | 5.5   | 3855       |             |         |
| SURF   | 10.75 | 197        |             |         |

\$ 125.29

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/22/2006 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Sand to 3800' and top with 5 sacks of cement. Perforate 5-1/2" casing at 875' and 350'. Run tubing to 875' and spot 50 sacks of cement. Pull tubing to 350' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/25/2006 4:30 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:  
5/22/2006 -- Sanded to 3780' and topped with 5 sacks of cement. Perforated 5-1/2" at 875' and 350'. Ran 2-3/8" tubing to 885' and spotted 50 sacks of cement. With 2% CaCl. Pulled tubing to 366' and circulated 400 sacks of cement to surface.  
5/23/2006 -- Checked top plug. Cement down at 135' inside the 5-1/2" casing and down at 40' in 10-3/4" x 5-1/2" annulus. Cut off wellhead.  
5/25/2006 -- Topped off top plug with 45 sacks of cement.  
5/26/2006 -- Witnessed closing of workover pit and covering of well. Leveled location.  
60/40 posmix with 4% gel by Copeland Acid & Cement, Inc. #30519

Perfs:  
**RECEIVED  
KCC DISTRICT #2  
JUN - 6 2006  
WICHITA, KS**

Remarks:  
Plugged through: TBG

District: 02 Signed Michael Wilson  
(TECHNICIAN)

6-28-06  
2006061864

*M*

**RECEIVED  
JUN 28 2006  
KCC WICHITA**

PCT