

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20626-00-00
Spot: SESWNW Sec/Twnshp/Rge: 33-17S-10W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: STEINERT B Well #: 1
County: ELLSWORTH Total Vertical Depth: 3276 feet

Operator License No.: 7030
Op Name: EVANS, JOHN ROY
Address: BOX 385 405 FOURTH STREET
CLAFLIN, KS 67525

String Size Depth (ft) Pulled (ft) Comment
PROD 5.5 3270
SURF 8.625 246

\$ 106.47

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/02/2006 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOES MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Sand 50' above perms and cap w/ 5 sxs. Pump 35 sxs @ 1300'. Pump 35 sxs @ 975' & circ w/ cmt from 300' to surf.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/02/2006 12:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 3220' and capped with 5 sacks of cement. 50 sacks of cement were pumped at 1700' because well began flowing fluid at 1700'. Casing was pulled to 975' and pumped 35 sacks of cement. Pulled casing to 300' and pumped 150 sacks of cement to circulate to surface.

235 sacks of 60/40 posmix with 4% gel

Copeland Cementing #30467

Perfs:

Top	Bot	Thru	Comments
3270	3276		
RECEIVED KCC DISTRICT #2 JUN - 5 2006 WICHITA, KS			

Remarks:

Plugged through: CSG

District: 02

Signed Greg Eves

(TECHNICIAN)

INVOICED
6-28-06
20060618.66

RECEIVED
JUN 28 2006
KCC WICHITA

m

PKT