

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21116-00-00
Spot: SESWSW Sec/Twnshp/Rge: 28-17S-10W
336 feet from S Section Line, 4376 feet from E Section Line
Lease Name: PETERMAN Well #: 3
County: ELLSWORTH Total Vertical Depth: 3348 feet

Operator License No.: 7030
Op Name: EVANS, JOHN ROY
Address: BOX 385 405 FOURTH STREET
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3348		100 SX
SURF	8.625	306		150 SX

108-81

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/13/2006 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Sand to 3280' and cap w/ 5 sxs cmt. Pump 35 sxs @ 1300'; 35 sxs @ 975'; and circ from 360' to surf.

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 05/31/2006 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 3230' and capped with 5 sacks of cement. Cut pipe at 2420' and pulled to 1300' where 35 sacks of cement were pumped. Pulled pipe to 975' and pumped 35 sacks of cement. Pulled pipe to 360' and pumped 180 sacks to circulate to surface.

250 sacks of 60/40 posmix with 4% gel

Copeland Cementing #30522

Perfs:

Top	Bot	Thru	Comments
3332	3348		OH ARB
3289	3292		

RECEIVED
KCC DISTRICT #2
JUN - 5 2006
WICHITA, KS

Remarks:
Plugged through: CSG

District: 02

Signed Greg Eves
(TECHNICIAN)

INVOICED
DATE 6-28-06
TEL. NO. 200 606.1866

RECEIVED
JUN 28 2006
KCC WICHITA

[Handwritten mark]

PKT