

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-20014-00-00
Spot: NWNE Sec/Twnshp/Rge: 24-22S-9E
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: BROWNING Well #: 1
County: CHASE Total Vertical Depth: 2562 feet

Operator License No.: 5721
Op Name: GLACIER PETROLEUM CO., INC.
Address: 825 COMMERCIAL STREET PO BOX 5
EMPORIA, KS 66801

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2437		75 SX CMT
SURF	8.625	200		100 SX CMT

83.27

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2006 10:00 AM
Plug Co. License No.: 5721 Plug Co. Name: GLACIER PETROLEUM CO., INC.
Proposal Rcvd. from: JEFF HAWES Company: GLACIER PETROLEUM CO., INC. Phone: (620) 342-1148

Proposed Plugging Method: Sand to 2310' and top with 5 sacks of cement. Perforate 5-1/2" casing at 250'. Run 2-3/8" to 250' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: NONE
Date/Time Plugging Completed: 03/02/2006 11:00 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 2310' and topped with 3 sacks of cement. Ran 2-3/8" tubing inside 5-1/2" casing to 250' and circulated cement to the surface. Ran 3/4" tubing in 8-5/8" x 5-1/2" annulus to 250' and circulated cement to the surface.

Used common cement by Consolidated Industrial Service, Inc. #8369

Perfs:

Top	Bot	Thru	Comments
2361	2372		

RECEIVED
KCC DISTRICT #2
JUN - 6 2006
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed Michael Wilson

(TECHNICIAN)

INVOICED
6-28-06
2006061807

B

RECEIVED
JUN 28 2006
KCC WICHITA

Form CP-2/3

PICT