

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-20019-00-01
Spot: NWSENE Sec/Twnshp/Rge: 24-22S-9E
3630 feet from S Section Line, 990 feet from E Section Line
Lease Name: BROWNING OWWO Well #: 2
County: CHASE Total Vertical Depth: 2500 feet

Operator License No.: 5721
Op Name: GLACIER PETROLEUM CO., INC.
Address: 825 COMMERCIAL STREET PO BOX 5
EMPORIA, KS 66801

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2500		75 SX CMT
SURF	8.625	203		100 SX CMT

83-27

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/02/2006 12:30 PM
Plug Co. License No.: 5721 Plug Co. Name: GLACIER PETROLEUM CO., INC.
Proposal Revd. from: JEFF HAWES Company: GLACIER PETROLEUM CO., INC. Phone: (620) 342-1148

Proposed Plugging Method: Sand to 2390' and top with 5 sacks of cement. Perforate 5-1/2" casing at 255'. Run 2-3/8" tubing to 255' and circulated cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: NONE
Date/Time Plugging Completed: 03/02/2006 2:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 2390' and topped with 3 sacks of cement. Perforated 5-1/2" casing at 250'. Ran 2-3/8" tubing to 250' and circulated 60 sacks of cement to the surface.
Used common cement by Consolidated Industrial Services, Inc. #8368.

Perfs:

Top	Bot	Thru	Comments
2442	2448		

**RECEIVED
KCC DISTRICT #2
JUN - 6 2006
WICHITA, KS**

Remarks:

Plugged through: TBG

District: 02

Signed Michael Wilson

(TECHNICIAN)

INVOICED
6-28-06
2006061867

RECEIVED
JUN 28 2006
KCC WICHITA

Form CP-2/3

P/KT