

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-21147-00-00  
Spot: SWSE Sec/Twnshp/Rge: 14-29S-18W  
660 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: WEDEL Well #: 1  
County: KIOWA Total Vertical Depth: 4864 feet

Operator License No.: 32158  
Op Name: H & B PETROLEUM CORP.  
Address: 130 E. ROSS, SUITE 103  
CLEARWATER, KS 67026

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4852	1178	WITH 175 SX CMT
SURF	8.625	433		WITH 350 SX CMT

# 158.08

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/20/2006 8:00 AM  
Plug Co. License No.: 33369 Plug Co. Name: XTREME WELL SERVICE, INC.  
Proposal Rcvd. from: AL HAMMERSMITH Company: H & B PETROLEUM Phone: (620) 584-6380

Proposed Plugging Method: SQUEEZE 4700 TO TD WITH 100 SACKS 60/40 POS. PLUG AT 1150 WITH 15 SACKS GEL & 50 SACKS 60/40 POS. PLUG AT 460 WITH 50 SACKS 60/40 POS. PLUG AT 40, CEMENT TO SURFACE. WILL TRY TO RECOVER 200' OF PIPE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE  
Date/Time Plugging Completed: 06/20/2006 9:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

IST PLUG PUMP 100 SX CMT WITH 100# HULLS. SQUEEZED FROM 4700' TO 4864'. LOCKED UP AT 2700#. 2ND PLUG AT 1150' WITH 15 SX GEL & 50 SX CMT. 3RD PLUG AT 530' WITH 120 SX CMT. 4TH PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4852	4864		
4848	4852		
4723	4730		
4713	4718		
3484	3488		

INVOICED


6-28-06

2006061868

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

*Steve Durrant*

(TECHNICIAN)

RECEIVED

JUN 28 2006

KCC WICHITA

Form CP-2/3

AGT