

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-073-30369-00-00  
Spot: NENWSE Sec/Twnshp/Rge: 17-25S-9E  
2440 feet from S Section Line, 1735 feet from E Section Line  
Lease Name: PERRIER Well #: 6  
County: GREENWOOD Total Vertical Depth: 2400 feet

Operator License No.: 5697  
Op Name: JACKSON BROS., L.L.C.  
Address: 116 EAST THIRD ST.  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2400	703	
SURF	8.625	38		

\$ 78.00

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/16/2006 8:00 AM  
Plug Co. License No.: 5684 Plug Co. Name: SAGE, LARRY GEORGE  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 50' CEMENT PLUG @ 2350' 50' CEMENT PLUG @ 900' 250' CEMENT PLUG TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/19/2006 12:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

BUILT ROCK BRIDGE @ 2300' ATOP OF PACKER STUCK IN CASING. DUMPED 5 SXS CEMENT WITH DUMP BALER, SHOT CASING @ 809' COULD NOT PULL, RESHOT CASING @ 703', PULLED CAING TO TO 670' PUMPED 25 SXS CEMENT. PULLED CASING TO 265' PUMPED 130 SXS CEMENT TO SURFACE. PULLED CASING OUT.

Perfs:

RECEIVED  
KCC DISTRICT #3  
JUN 26 2006  
CHANUTE, KS

INVOICED  
7-5-06  
2007060007

Remarks:

Plugged through: CSG

District: 03

Signed Niko Heffern  
(TECHNICIAN)

RECEIVED  
JUN 30 2006  
KCC WICHITA

Form CP-2/3

PKT