

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20370-00-00
Spot: S2NESWNW Sec/Twnshp/Rge: 14-19S-10W
3530 feet from S Section Line, 4290 feet from E Section Line
Lease Name: APPLETON Well #: 3
County: RICE Total Vertical Depth: 3455 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3376		
SURF	8.625	235		
T1	2.375	3376		

\$ 112.29

Well Type: SWD UIC Docket No: D20190.0 Date/Time to Plug: 05/26/2006 9:00 AM
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 05/26/2006 11:15 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Attempted to pull tubing out of the well on 5/23/2006. Tubing parted approximately 2 jts down. Used 4-1/2" wash-over pipe and mill shoe to mill down to approximately 256'. When tripping out with wash-over pipe, there were pieces of tubing, tubing collars, and what appeared to be casing. Ran 1" tubing on down to approximately 295' and circulated cement to surface. Cement circulated on backside of 5-1/2". Connected to 5-1/2" and pressured to 400 lbs.

Copeland cement ticket #C030456

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3376	3456		

RECEIVED
KCC DISTRICT #2
JUN - 9 2006
WICHITA, KS

INVOICED

6-28-06
2006061874

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

RECEIVED
JUN 28 2006
KCC WICHITA

[Handwritten mark]

[Handwritten mark]