

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-031-20939-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 32-22S-14E
3826 feet from S Section Line, 2313 feet from E Section Line
Lease Name: L SCHNEIDER Well #: 1
County: COFFEY Total Vertical Depth: 1365 feet

Operator License No.: 8093
Op Name: HAAS, GARY L. DBA GARY HAAS - OIL
Address: 114 SOUTH MAIN
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1365	0	
SURF	7	40	0	

\$ 44.36

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/23/2006 1:00 PM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: GARY HAAS Company: GARY HAAS Phone: (620) 836-4551

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 1365' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/23/2006 2:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 700PSI.

RECEIVED
KCC DISTRICT #3
JUN 21 2006 CPT
CHANUTE, KS

Perfs:

INVOICED
DATE 7-5-06
2007660006

Remarks: SPOT LOCATION FOR THIS WELL WAS ESTABLISHED VIA GPS SURVEY AS SESSION POINT NO.3.

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

RECEIVED
JUN 30 2006
KCC WICHITA

PKT