

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-031-20954-00-00
Spot: SESWNE Sec/Twnshp/Rge: 32-22S-14E
3040 feet from S Section Line, 1900 feet from E Section Line
Lease Name: E SCHNEIDER Well #: 3
County: COFFEY Total Vertical Depth: 1365 feet

Operator License No.: 8093
Op Name: HAAS, GARY L. DBA GARY HAAS - OIL
Address: 114 SOUTH MAIN
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1365	0	
SURF	7	40	0	

\$144.36

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/23/2006 6:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: GARY HAAS Company: GARY HAAS Phone: (620) 836-4551

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 1365' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 05/23/2006 7:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 600PSI. 27 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED
KCC DISTRICT #3
JUN 21 2006
CHANUTE, KS
CPT

INVOICED
7-5-06
2007060006

Remarks: SPOT LOCATION DETERMINED VIA GPS SURVEY AS GPS SESSION POINT NO.SCH4.

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

RECEIVED
JUN 30 2006
KCC WICHITA

CPT