

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-03251-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 14-10S-20W  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: STITHEM Well #: 17  
County: ROOKS Total Vertical Depth: 3815 feet

Operator License No.: 32638  
Op Name: NADEL AND GUSSMAN, LLC  
Address: 15 E. 5TH, SUITE 3200  
TULSA, OK 74103

| String | Size | Depth (ft) | Pulled (ft) | Comment           |
|--------|------|------------|-------------|-------------------|
| PROD   | 7    | 3810       | 0           | w/unknown sxs cmt |
| SURF   | 10   | 160        | 0           | w/unknown sxs cmt |

#123.99

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/07/2006 1:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: ART ROLO Company: NADEL AND GUSSMAN, LLC Phone: (785) 737-3530

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 10% gel - 1400# hulls.  
Ordered 200 sxs common - 3% cc with 500# hulls.  
Tubing parted (sanded in). Recovered 1697' rods and 1369' tubing.  
Decided to P&A. Could not get below 1697'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/07/2006 6:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to top of fish 1369'.  
Allied pumped 135 sxs 60/40 pozmix - 10% gel neat. Circulated cement.  
PTOH. Squeezed with 225 sxs cement with 1100# hulls - on vacuum - shut in.  
Hooked up to backside and pumped 100 sxs cement with 300# hulls.  
Max. P.S.I. 500#. S.I.P. 200#.  
Waited on more cement two hours.  
Cement 600' from surface.  
Allied pumped 100 sxs common - 3% cc with 200# hulls - hole full of cement.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

**INVOICED**  
6-28-06  
2006061874

District: 04

Signed Richard Williams  
(TECHNICIAN)

RECEIVED  
JUN 28 2006  
KCC WICHITA

Form CP-2/3

JUN 12 2006

PLT

NADEL & GUSSMAN

#17 STITHAM

14-10-20W 22  
NW NW NE

Contr. RESERVE DRILLING

ROOKS

County

E 2230

Comm.

Comp.

8-1-52

IP

D & A

| Tops      | Depth | Datum |
|-----------|-------|-------|
| HEEB      | 3453  | -1223 |
| LANS      | 3490  | -1260 |
| CONG      | 3736  | -1506 |
| WEATH ARB | 3805  | -1575 |
| ARB       | 3809  | -1579 |
| TD        | 3815  | -1585 |

Casing

10" 160

5" 3810

DD 3815: WTR

MARCOTTE POOL

|   |   |   |   |
|---|---|---|---|
| + | + | + | + |
| + | + | + | + |
| + | + | + | + |

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS