

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-01849-00-00
Spot: SESWNE Sec/Twnshp/Rge: 20-12S-15W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MILLER C Well #: 2
County: RUSSELL Total Vertical Depth: 3326 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3270	0	w/unknown sxs cmt
SURF	8.625	236	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/14/2006 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/14/2006 12:40 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Perforated at 500' - 950' - 1575'.
Fluid at 1050'.
TD with wireline was 3290'.
Tied onto backside and pumped 50 sxs 60/40 pozmix - 10% gel cement.
Max. P.S.I. 500#. S.I.P. 100#.
Tied onto casing and pumped 220 sxs cement with 500# hulls.
Max. P.S.I. 800#. S.I.P. 600#.

Remarks: QUALITY CEMENT.

Plugged through: TBG

RECEIVED
JUL 05 2006
KCC WICHITA

District: 04

105

Signed

Case Morris

(TECHNICIAN)

[Handwritten signature]

JONES, SHELburnE & FARMER #2 C MILLER 20-12-15W 33
 SE SW NE


Contr. JONES, SHEL & FARMER RUSSELL County

E 1864RB Comm. 10-17-57 Comp. 11-22-57 IP 25 BOPD

Tops	Depth	Datum
ANH	910	954
TOP	2732	-868
HFFB	2958	-1094
TOR	2978	-1114
LANS	3008	-1144
GORH SND	3268	-1404
CONG	3288	-1424
ARB	3313	-1449
TD	3326	-1462

Casing
 8" 236
 5" 3270
 PERF 4/3038-43: 2½ GO & 2½ GWPB
 ACID 1250: 5.20 BOPB, 25% WTR
 PLUG 3030: 6/3018-22: ACID 3000
 8.16 BOPB, 4% WTR

FAIRPORT POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS