

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-01848-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 20-12S-15W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: MILLER C Well #: 1  
County: RUSSELL Total Vertical Depth: 3300 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3122	0	w/unknown sxs cmt
SURF	8.625	200	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/15/2006 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed  
Plugging  
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/15/2006 12:00 PM KCC Agent: CASE MORRIS

**Actual Plugging Report:**

**Perfs:**

Ran in with tubing and bit. Hit several bridges - then hit steel at 718'.  
POOH. Ran in open ended to 713'.  
Pumped 50 sxs 60/40 pozmix - 10% gel cement.  
Pulled to 450' and circulated with 50 sxs cement.  
POOH. Tied onto casing and pumped 140 sxs cement.  
Max. P.S.I. 1000#. S.I.P. 600#.  
Tied onto backside and pumped 110 sxs cement.  
Max. P.S.I. 800#. S.I.P. 200#.

Remarks: QUALITY CEMENT.

Plugged through: TBG

RECEIVED  
JUL 05 2006  
KCC WICHITA

District: 04

Signed Case Morris

(TECHNICIAN)

JUN 28 2006

20-12-15W

JONES, SHELburnE & FARMER #1 CLEEVE MILLER SW SW NE 33

Contr. JONES, SHELburnE & FARMER RUSSELL County

E 1838RB Comm. Comp. 12-14-56 IP 2'5 BOPD

Tops	Depth	Datum
ANH	886	952
TOP	2706	-868
HEEB	2925	-1087
TOR	2945	-1107
LANS	2974	-1136
B/KC	3200	-1362
GORH SD	3251	-1413
CONG	3269	-1431
ARB	3283	-1445
TD	3300	-1462

Casing  
 8" 200  
 5" 3122  
 DST 2872-2915/1 HR, 105' MDY SW, BHP 920#  
 DST 2978-92/1 HR, 470' G, 70' O & GCM, BHP 300#  
 DST 3002-21/1 HR, 145' HO & GCM, 930' G, 6' WTR, BHP 440#  
 DST 3255-65/1 HR, 15' MDY SW, BHP 0#  
 DST 3284-91/30", 20' RTRY M, BHP 980#  
 PERF 3010-15: ACID 1250: 13 BOPH

FAIRPORT

+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS