

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02008-00-00  
Spot: S2S2SW Sec/Twnshp/Rge: 3-10S-20W  
330 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: NUTSCH Well #: 3  
County: ROOKS Total Vertical Depth: 3815 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3808	0	w/125 sxs cmt
SURF	8.625	132	0	w/100 sxs cmt

\$ 123.99

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/28/2006 9:00 AM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6110

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix -10% gel - 600# hulls - 21 sxs gel spacer.  
PBTD 3700'. Waited on cement trucks 1 1/2 hrs.  
Squeeze jobs: 1953-1119' w/280 sxs; 1969-1250' w/133 sxs; 1980-2080' w/300 sxs; 1994-2668'-2700' w/150 sxs.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/28/2006 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3700'. Allied pumped 25 sxs cement with 200# hulls.  
Pulled tubing to 3360'. Allied pumped 10 sxs gel neat, followed with 11 sxs gel with 250# hulls.  
Pulled tubing to 1750'. Allied pumped 100 sxs cement with 150# hulls - cwc.  
PTOH. Squeezed 5 1/2" casing with 20 sxs cement.  
Max P.S.I. 500#. S.I.P. 500#.  
Hooked up to backside and pumped 50 sxs cement.  
S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3718	3722		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

**INVOICED**  
DATE 7/5/06  
NO. 2007060001

District: 04

AD.

Signed Richard Williams  
(TECHNICIAN)

JUN 29 2006

RECEIVED  
JUN 30 2006  
KCC WICHITA

Form CP-2/3

PEI

WICHITA

WADICEN

HEATHMAN DRILLING CO., INC. # 3 NUTSCH 3-10-20W  
S2 S2 SW

Contr. \_\_\_\_\_ ROOKS \_\_\_\_\_ County


E 22 1/2 RB Comm. \_\_\_\_\_ Comp. 5-26-50 IP 2288 BOPD

DRAW DOWN

Tops	Depth	Datum
ANH	1720	+527
HEER	3173	-1226
LANS	3513	-1266
B/KC	3739	-1492
CONG	3772	-1525
SIMP	3786	-1539
SIMP DOI	3792	-1545
ARB	3805	-1558
T.D.	3815	-1568

Casing  
8" 133  
5" 3807  
ACID 2000  
PMP 22 BOPD

PALCO SE POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS