

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21661-00-00
Spot: S2SENWSW Sec/Twnshp/Rge: 23-12S-22W
1500 feet from S Section Line, 4290 feet from E Section Line
Lease Name: STECKLINE Well #: 2
County: TREGO Total Vertical Depth: 4089 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4085	0	250 SX CMT
SURF	8.625	339	0	180 SX CMT

\$ 132.89

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/22/2006 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered 300 sxs cement and 500# hulls.
Perfed at 1600' - 900' - 300'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/22/2006 1:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Fish at 1600'.
Three attempts at pulling casing - failed.
Ran tubing to 1590' - circulated with 170 sxs cement - pulled all tubing.
Squeezed 4 1/2" casing with 20 sxs cement.
Max. P.S.I. 350#. S.I.P. 350#.
Tied to annulus (4 1/2" x 8 5/8") - squeezed 50 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.
Total of 240 sxs 60/40 pozmix - 10% gel.

Perfs:

Remarks: COPELAND ACID & CEMENTING. ATS-WATER.

Plugged through: TBG

INVOICED

DATE 7-5-06
2007060002

District: 04

JD

Signed

Roger Moses
(TECHNICIAN)

RECEIVED

JUN 30 2006

KCC WICHITA

Form CP-2/3

JUN 26 2006

PRT

INDEXED

JOHN JAY DARRAH, JR.
405 CENTURY PLAZA BLDG. #2 STECKLINE 23-12-22W
WICHITA, KS 67202 150'S.
CONTR KAW DRILLING CO. CITY TREGO C SE NW SW

GEOL BETH FUHR FIELD OGALLAH NO.

ELV 2386 KB SPD 1/27/85 CARD ISSUED 5/9/85 IP P 30 BO & 30 BWP
2375 GL ARB 4074-4088

+	+
+	+
+	+

SMP	Tops	Depth/Datum
ANH	1805+	581
TOP	3420	1034
HEEB	3626	1240
TOR	3658	1272
LANS	3671	1285
BKC	3913	1527
MARM	4002	1616
ARB	4065	1679
PBD	4086	1700
RTD	4089	1703

API 15-195-21,661
8 5/8 " 339 / 180SX, 4 1/2 " 4085 / 250SX
DST (1) 4029-4089 (MARM, ARB) / 30-30-45-30. (1ST OP) FB /
8", (2ND OP) FB / 6", REC 200" OIL & WCM, SIP 1168-1113#.
FP 100-111 / 233-256#, HP 2125-2125#
MICT - CO, PF (ARB) 4074-4084, AC 500G, SWB DWN, GSO, PF
(ARB) 4084-4088, AC 1000G, SWB DWN, GSO, T&R, POP, P 30
BO & 30 BWP, 3/6/85

CORRECTION: 1/29/85 - ORIGINALLY FIRST
REPORTED AS 68'W, C W/2 NE SW

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS