

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-03040-00-00  
Spot: SWSENW Sec/Twnshp/Rge: 36-10S-21W  
2970 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: LEWIS C V Well #: 4  
County: GRAHAM Total Vertical Depth: 3695 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 SOUTH ST. FRANCIS PO BOX 2757  
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3684	0	125 SX CMT
SURF	8.625	185	0	125 SX CMT

# 120.09

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/23/2006 9:00 AM  
Plug Co. License No.: 5552 Plug Co. Name: GORE OIL COMPANY  
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 345-1597

Proposed Plugging Method: Ordered out 300 sxs Swift Multi-Density Cement with 750# hulls.  
Low fluid level.  
Prior squeeze job: 1970-987' w/150 sxs; 1972-1245'-1300' w/200 sxs; 1984-1050' w/175 sxs. 1987-1075'-1107' w/100 sxs;  
2006-1026'-1148' w/100 sxs; 2006-2287'-2318' w/100 sxs.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/23/2006 11:45 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Swift Services pumped 175 sxs Swift Multi-Density Cement with 750# hulls.  
Max. P.S.I. 700#. S.I.P. 50#.  
Hole full of cement.  
Hooked up to backside and pumped 15 sxs cement  
Max. P.S.I. 400#. Blew hole below 8 5/8" collar.  
Hole full of cement.

Perfs:

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

INVOICED  
7-5-06  
2007060005

District: 04

Signed Richard Williams  
(TECHNICIAN)

RECEIVED  
JUN 30 2006  
KCC WICHITA

JUN 28 2006

PCT

HARRY GORE

#4 C V LEWIS

36-10-21W  
SW SE NW

Contr. VEEDER SUPPLY & DEV COMPANY GRAHAM County


E 2127RB Comm. 8-27-54 IP 454 BOPD  
PHY POT

Tops	Depth	Datum
ANH	595	1532
TOP	3144	-1017
HEEB	3350	-1223
TOR	3374	-1247
KC	3390	-1263
B/KC	3618	-1491
CONG	3660	-1533
ARB	3683	-1556
TD	3685	-1558

Casing  
5" 3684

CO 3685: PMP 22 BOPH/  
10 HRS:

WHITE SW POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS