

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00928-00-02
Spot: SWSWNE Sec/Twnshp/Rge: 11-14S-18W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: EMMA LEIKER OWWO Well #: 1
County: ELLIS Total Vertical Depth: 3915 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	16	229		200 SX CMT
PROD	4.5	3880	0	100 SX CMT
SURF	8.625	1190	0	475 SX CMT

\$ 127.24

Well Type: SWD UIC Docket No: D20804.0 Date/Time to Plug: 06/27/2006 9:30 AM
Plug Co. License No.: 33674 Plug Co. Name: DAVE'S WELL SERVICE, LLC
Proposal Rcvd. from: TERRY MORRIS Company: GLM COMPANY Phone: (785) 483-2123

Proposed Plugging Method: Ordered 100 sxs 60/40 pozmix - 10% gel with 1/4# flocele per sack and 500# hulls.
Well previously had 160 sxs pumped down 4 1/2" casing and displaced to 1000' on 03/30/2004-Allied Cementing Company ticket #16839.
Well was intended to be a water supply well for Osage Resources LLC.
Backside was not cemented.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/27/2006 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Dave's Well Service washed down well with tubing to 512' to top of soft cement.
Allied rigged to tubing and pumped 50 sxs 60/40 pozmix to circulate cement to surface.
Cement also circulated out of 8 5/8" casing.
Pulled tubing - shut in 8 5/8" backside - rigged to 4 1/2" casing with a swedge and pumped 10 sxs cement.
Max. P.S.I. 500#. S.I.P. 275#.

Perfs:

Top	Bot	Thru	Comments
3880	3915	OH	

INVOICED
7-5-06
2007060008

Remarks: ALLIED CEMENTING COMPANY-TICKET #25585.

Plugged through: TBG

District: 04

Signed Pat Staab
(TECHNICIAN)

①

JUN 29 2006

RECEIVED
JUN 30 2006
KCC WICHITA

Form CP-2/3

PPT

