

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22274-00-00
Spot: NENESW Sec/Twnshp/Rge: 11-14S-18W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease Name: LEIKER J Well #: 1
County: ELLIS Total Vertical Depth: 3590 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-------------------|
| PROD | 4.5 | 3576 | 0 | w/unknown sxs cmt |
| SURF | 8.625 | 1196 | 0 | w/unknown sxs cmt |

\$ 116.68

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/26/2006 12:00 PM
Plug Co. License No.: 33674 Plug Co. Name: DAVE'S WELL SERVICE, LLC
Proposal Rcvd. from: DON REINHART Company: GLM COMPANY Phone: (785) 483-2123

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Well squeezed 3025' - 1925'; 475'-675'.

Plugging Proposal Received By: ROGER MOSES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/26/2006 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

TIH with tubing to 3250' - mixed and pumped 100 sxs cement with 300# hulls.
Pulled up to 1600' - circulated cement with 80 sxs and 200# hulls.
POOH Swaged onto 4 1/2" and topped with 15 sxs cement.
S.I.P. 500#.
Hooked up to the annulus - instant 500#.

INVOICED
DATE 7-5-06
2007060008

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

RECEIVED

JUN 30 2006

KCC WICHITA

Form CP-2/3

JUN 29 2006

ACT

