

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20604-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 23-12S-22W  
1650 feet from N Section Line, 990 feet from W Section Line  
Lease Name: NIXON Well #: 1  
County: TREGO Total Vertical Depth: 4098 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 NORTH MARKET, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4090	0	200 SX CMT
SURF	8.625	273	0	180 SX CMT

# 133.19

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/23/2006 11:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 729-3410

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/23/2006 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3210' and topped with 4 sxs using a dump bailer.  
Perforated casing at 1800' - mixed and pumped 75 sxs cement with 200# hulls.  
Shot casing at 850' - would not come free - came up to 642'.  
Shot casing free - spotted 50 sxs cement with 100# hulls.  
Pulled up to 250' and circulated cement with 75 sxs and 200# hulls.  
POOH. Hole full of cement.

Perfs:

Top	Bot	Thru	Comments
4090	4098		
4076	4086		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

INVOICED  
DATE 7-5-06  
2007060070

District: 04

Signed Jay Pfeifer (TECHNICIAN)

RECEIVED

JUN 30 2006

KCC WICHITA

Form CP-2/3

JUN 26 2006

PCT

