

6 020410

10-11-87

API NUMBER 15- 665-22,406-08-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW SE SW, SEC. 16, T. 7 S, R. 23 W/E  
330 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5923

Lease Name Brant Well # 1

Operator: American Petr Co. Inc.

County Graham 115.38

Name & Address 3500 North Rock Road

Well Total Depth 3550 feet

Building #1300

Conductor Pipe: Size feet

Wichita, Kansas 67226

Surface Casing: Size 8 5/8 feet 212.58

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Emphasis License Number 8241

Address Russell, Kansas

Company to plug at: Hour: Day: Month: Oct. Year: 19 87

Plugging proposal received from Tom Alm

(company name) (phone)

were: Order 200 sks 60/40 Pozmix 6% Gel 3% Cal Cl 1 sk Flocele and 8 5/8" plug.

Spot with drill pipe with no less than 36 vic. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: Midnight Day: 11 Month: October Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2100' w/25 sks Cir mud between all plugs.

2nd plug at 1270' w/100 sks F. C.

3rd plug at 220' w/40 sks

4th plug at 40' w/10 sks / wiper plug

15 sks in rat hole 10 sks in mouse hole.

RECEIVED STATE CORPORATION COMMISSION  
10/23/87  
OCT 23 1987  
RECEIVED STATE CORPORATION COMMISSION  
Wichita, Kansas  
OCT 23 1987

Remarks: Cemented by Allied

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE 10-26-87

INV. NO. 18646

Signed Gilbert Balthazor (TECHNICIAN)

Gilbert Balthazor