

4-20-88

6 031072

API NUMBER 15-045-02956-00-00¹⁹⁵⁸

C NW NE, SEC. 25, T 7 S, R 23 (W)E

4620 feet from S section line

1980 feet from E section line

Lease Name Fabricius U Well # 1 02

County Graham 119.44

Well Total Depth 3675 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 220

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: Oxy USA

Name & Address: 3545 NW 58th St.

Oklahoma City, Ok. 73112

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Kansas

Company to plug at: Hour: PM Day: 20 Month: April Year: 19 88

Plugging proposal received from Mr. Pringle

(company name) Oxy (phone)

were: 8 5/8" set @ 220' w/175 sx cwc. 5 1/2" set @ 3675' w/ 125 sx. PBTD 3640'. Perf 3617-28'.

Shots in anhy @ 1839' and below Dakota @ 925'. Order 300 sx cement blend w/ 6 sx hulls.

Halliburton Cmt. Co. OWS Water truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6:00PM Day: 20 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" casing w/ 200 sx cement w/ 5 sx hulls in last 100 sx

to maximum psi 1000#. Close in psi 600#. Annulus circulated from 5 1/2". Pumped on

annulus. Casing blew out shut in. Plug complete.

RECEIVED
MAY 18 1988
5/18/88

CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (Will be billed later) observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

DATE 5-20-88

INV. NO. 20802

Carl Goodrow