

6 031082

4-21-88

API NUMBER 15-065-02957-00-00
1958

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE NW, SEC. 25, T 7 S, R 23 W/E
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Fabricius U Well # 103

Operator: Oxy Usa

County Graham 118.63

Name & Address 3545 N.W. 58th St.

Well Total Depth 3650 feet

Oklahoma City, Ok. 73112

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 223

Abandoned Oil Well X Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 21 Month: April Year: 19 88

Plugging proposal received from Mr. Pringle

(company name) Oxy (phone)

were: 8 5/8" set at 223' w/150 sks cwc 5 1/2" set at 3650' w/125 sks.

PBTD 3628'. Perf 3599' - 3609'. Shots in Anhy at 1815' and below Dakota at 900'

Order 300 sks Cement Blend w/6 sks Hulls. Halliburton Cement Co. OWS Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 1:00 PM Day: 21 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" casing w/200 sks cement w/5 sks Hulls in last 100 sks cement. To max Psi 500#. Close in Psi 350#. Squeezed 8 5/8" w/15 sks cement to max Psi 400#. Close in Psi 300#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

MAY 17 1988 5/17/88

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED
to observe this plugging.

DATE 5-19-88

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 20779

Carl Goodrow