

6 031074

4-20-88 15-065-02958-00-01

API NUMBER 15- 1958

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C SW NE, SEC. 25, T 7 S, R 23 W/E

3300 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Fabricius U Well # 104W

Operator: Oxy USA

County Graham 119.44

Name & Address 3545 NW 58th St.

Well Total Depth 3675 feet

Oklahoma City, Ok. 73112

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 223

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Kansas

Company to plug at: Hour: PM Day: 20 Month: April Year: 19 88

Plugging proposal received from Mr. Pringle

(company name) Oxy (phone)

were: 8 5/8" set @ 223' w/ 150 sx cwc. 5 1/2" set @ 3675' w/ 125 sx. PBTD 3581' Perf 3612-22'  
shots in any @ 1825' and below Dakota @ 900'. order 300 sx. cement blend and  
6 sx hulls. Halliburton Cmt. Co. OWS Water trucks.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:15PM Day: 20 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" casing w/ 150sx of cement w/ 45 sx of hulls in  
last 50 sx. to maximum psi 1000#. Close in psi 600#. Squeezed annulus w/ 50 sx cement  
w/ 15 sx hulls to maximum psi 450#. Close in psi 150#. Plug complete

RECEIVED  
STATE CORPORATION COMMISSION

MAY 18 1988 5/18/88

Remarks: (If additional description is necessary, use BACK of this form.)

(If observed) observe this plugging.

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow

INVOICED  
DATE 5-20-88  
INV. NO. 20808