

4-20-88

6 031075

API NUMBER 15-065-02955-00-04¹⁹⁵⁸

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE SE, SEC. 24, T 7 S, R 23 (W) E

660 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Fabricius U Well # 202 W

Operator: Oxy USA

County Graham 120.25

Name & Address 3545 NW 58th St.

Well Total Depth 3700 feet

Oklahoma City, Ok. 73112

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 229

Abandoned Oil Well Gas Well Input Well X SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 20 Month: April Year: 19 88

Plugging proposal received from Mr. Pringle

(company name) Oxy (phone)

were: 8 5/8" set @ 229' w/ 150 sx cwc. 5 1/2" set @ 3700' w/ 100 sx. PBTD 3670' Perf @ 3638-54'
Shots in any @ 1855' and below Dakota @ 925'. Order 300 sx cement blend and 6 sx
hulls. Halliburton Cmt. Co. OWS Water truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 12:00PM Day: 20 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" casing w/275 sx cement w/ 5 sx hulls in last 100 sx to
maximum psi 500#. Close in psi 300#. Squeezed 8 5/8" w/ 25 sx cement w/ 1 sx hulls
to maximum psi 400#. Close in psi 150#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1988 5/18/88

Remarks: (If additional description use BACK of this form.)
Conservation Division
Wichita, Kansas

INVOICED
Please observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

DATE 5-20-88

INV. NO. 20805