

6 031065

4-18-88 15-065-03081-00369

API NUMBER 15- 1959

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW SW, SEC. 24, T 7 S, R 23
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5447
Wichita, Kansas

Lease Name Fabricius U Well # 502W
County Graham 112.78
Well Total Depth 3740 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 226

Operator: Oxy USA
Name & Address: 3545 NW 58th St.
Oklahoma City, Ok. 73112

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton License Number _____
Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 18 Month: April Year: 19 88

Plugging proposal received from Mr. Pringle
(company name) Oxy (phone) _____

were: 8 5/8" set at 226' w/175 sks. 5 1/2" set at 3740' w/125 sks. PBTD 3712'.
Perfs 3683' - 98'. Shots at 1315' Anhy and 1005' below Dakota.
Order 300 sks Cement Blend and 6 sks Hulls. Halliburton Cement Co. OWS Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____
Operations Completed: Hour: 12:40 PM Day: 18 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Squeeze 5 1/2" casing w/75 Cement Blend w/4 sks Hulls mixed
in last few sks. Hole locked upon pressure stopped at 750# basked off to 200#. Closed in.
Squeezed annulus w/39 sks w/1 sk Hulls to maximum Psi 300#. Close in 300#. Plug
complete.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 6-27-88
INV. NO. 26035

Signed Carl Goodrow
(TECHNICIAN)