

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22881-00-00
Spot: N27ENENW ^{SE (W/3/1/1/0)} Sec/Twnshp/Rge: 31-7S-23W
4458 feet from S Section Line, 2980 feet from E Section Line
Lease/Unit Name: BETHELL Well Number: B-1
County: GRAHAM Total Vertical Depth: 3800 feet

Operator License No.: 30076
Op Name: ANDERSON, ANDY DBA A & A PRODU
Address: PO BOX 100
HILL CITY, KS 67642

Surface Casing Size: 8.625 feet: 205 **8/23.50**

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/18/2003 1:00 AM

Plug Co. License No.: 30076 Plug Co. Name: ANDERSON, ANDY DBA A & A PRODUCTION

Proposal Rcvd. from: DARRELL ANDERSON Company: ANDERSON, ANDY DBA A & A PR Phone: (785) 421-6266

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 02/18/2003 2:00 AM

Witness Type: Plugging Operations Were Not Witnessed
KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 205' w/145 sxs cement.
1st. Plug at 2000' w/25 sxs cement.
2nd. Plug at 1200' w/100 sxs cement.
3rd. Plug at 260' w/40 sxs cement.
4th. Plug at 40' w/10 sxs cement. 8 5/8" wiper plug.
Rathole with 15 sxs.
Dakota 840'.
Anhydrite 1979' - 2012'.

RECEIVED
MAR 06 2003
KCC WICHITA
3/6/03

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

HO-

Signed Roger L. Moses
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 3-6-03
INV. NO. 2003061275

MAR 03 2003