

6 031067

4-18-88

API NUMBER 15-045-03084-00-00  
1959

C SE NE, SEC. 26, T 7 S, R 23 WE

3300 feet from S section line

660 feet from E section line

Lease Name Febricius UWell # 301

County Graham 121.23

Well Total Depth 3730 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 223

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: Oxy USA

Name & Address 3545 NW 58th St.

Oklahoma City, Oklahoma 73112

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 18 Month: April Year: 19 88

Plugging proposal received from Mr. Pringle

(company name) Oxy (phone)

were: 8 5/8" set at 223' w/175 sks 5 1/2" set at 3730' w/125 sks PRTD 3702'

Perf 3679' - 96'. Shots at 1900' Anhy and at 940' below Dakota.

Order 300 sks Cement Blend 6 sks Hulls. Halliburton Cement Co.

OWS Water Trucks.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:45PM Day: 18 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Squeeze 5 1/2" casing w/180 sks cement w/5 sks Hulls.

in last 80 sks to max Psi 1000#. Close in Psi 300#. Test Annulus w/2 sks cement

Lock up. Plug complete.

RECEIVED

MAY 17 1988

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: 5/17/88

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Carl Goodrow  
(TECHNICIAN)

Carl Goodrow

DATE 5-19-88

INV. NO. 20778