

To: 6 031069
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-18-88
API NUMBER 15-065-03095-00-01

C NE SE, SEC. 26, T 7 S, R 23 W/E
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Fabricius U Well # 302 W

Operator: Oxy USA
Name & Address 3545 NW 58th St.
Oklahoma City, Ok. 73112

County Graham 122.04
Well Total Depth 3755 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 226

Abandoned Oil Well Gas Well Input Well X SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 18 Month: April Year: 1988

Plugging proposal received from Mr. Pringle

(company name) Oxy USA (phone)

were: 8 5/8" set at 226' w/165 sks cwc 5 1/2" set at 3755' w/125 sks.

Perf at 3692' - 3706'. Shots in Anhy at 1905' and below

Dakota at 980'. Order 300 sks Cement Blend w/6 sks Hulls.

Halliburton Cement Co. OWS Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 6:20PM Day: 18 Month: April Year: 1988

ACTUAL PLUGGING REPORT Squeezed 5 1/2" casing w/250 sks Cement Blend w/5 sks Hulls
in with last 100 sks cement to maximum Psi 500#. Close in Psi 300#.

Squeezed annulus w/2 sks cement to maximum Psi 500#. Close in 500#. Plug complete.

RECEIVED
MAY 10 1988 5/18/88

Remarks: CONSERVATION DIVISION
Wichita, Kansas
(If additional description is necessary, use BACK of this form.)

INVOICED serve this plugging.

DATE 5-20-88

INV. NO. 20803

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow