

6 010308

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-22142000
SE, SEC. 27, T. 7 S, R 23 W/8
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8925

Operator: Liberty Oper. & Comp.
Name & Address: 308 W. Mill
Plainville KS.

Lease Name Morris Well # 1
County Graham 126.10
Well Total Depth 3880 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 254 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Pioneer Drlg License Number 5665
Address Same

Company to plug at: Hour: AM Day: 18 Month: 3 Year: 19 85

Plugging proposal received from John Walker
(company name) Pioneer Drlg. (phone) _____

were: order 185 sx cem. 30/50 portmix 6% gel 3% c.c.
Heavy mud between all plugs
Pump cem. down drill pipe

Elev. 2374 Anhydrite 2042-73 Arbuckle No
Dakota. 1400 Plugging Proposal Received by Dale F. Balchazo
974 = 1270 (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ (None)

Operations Completed: Hour: 3:45 AM Day: 18 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT circ. @ 2060 for 15 mi.

25 SX @ 2060
100 SX @ 1270 w. 1/2 SX flow Seal.
40 SX @ 270
10 SX @ 40 on Solid Bridge
10 SX in Rat Hole

Remarks: cem. Co Allied
(If additional description is necessary, use BACK of this form.)

I (did) (did not) observe this plugging.

DATE 3-26-85
INSTR. 7442
3-18

Signed Dale F. Balchazo
(TECHNICIAN)
3-22-85
7