

State of Kansas



15-163-20040-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 1967

CONSERVATION DIVISION
Wichita, Kansas

8/7/67

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Walker of Rains & Williamson has this
date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza Wichita, Kansas

Lease Name: Gager Well No. 1

Location: SE SE SW Sec. 29 Twp. 8 Rge. 16 (E)(W) X

County Rooks Total Depth 3475 3660 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 680' and displace
90 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulla and 8 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Red Z. Massey
Conservation Division Agent