



15-163-20146-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. - 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 6 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 11/6/68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Gustus of Leben Drlg., Inc. has this date requested permission to plug the following described well:

Mr. Gustus guarantees payment of the plugging fee.

Operator's full Name: Tilco, Et al

Complete Address: 815 Wichita Plaza Wichita, Ks.

Lease Name: Brown Well No. 1

Location: SW SW SE Sec. 32 Twp. 8 Rge. 16 (E)(W) X

County: Rooks Total Depth 3330 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Gustus was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace
70 sc cement thru drill pipe. Heavy mud to 180' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Pro. F. Massey
 Conservation Division Agent