

State of Kansas



15-163-20815-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1978
CONSERVATION DIVISION
Wichita, Kansas
6-27-78

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Weiler of Shields Drlg. has this date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Thomas E. Black d/b/a Black Petroleum Co.

Complete Address: 545 O. W. Garvey Bldg., Wichita, Ks.

Lease Name: Bemis "A" Well No. 1

Location: C W/2 W/2 SE/4 Sec. 27 Twp. 8 Rge. (E)(W) 17

County: Rooks Total Depth 3480' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Weiler was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 550' thru drill

pipe. Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

L. M. Massey
Conservation Division Agent