


KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy



API # 15 - 185-22,771 - CO-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date \_\_\_\_\_.

Well Operator: F.G. Holl Company, L.L.C. KCC License #: 5056

Address: 9431 E. Central, Suite 100 City: Wichita  
(Owner / Company Name) (Operator's)

State: Kansas Zip Code: 67206 Contact Phone: (316) 684 - 8481

Lease: BIGGS Well #: 1-15 Sec. 15 Twp. 24 S. R. 15  East  West

- NW - NW - NW Spot Location / QQQQ County: Edwards STAFFORD

4950 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

4950 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8" Set at: 268' Cemented with: 165 Sacks

Production Casing Size: 4-1/2" Set at: 4234' Cemented with: 225 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4059', 4075' - 4078', 4084' - 4087', 4094' - 4107'

Elevation: 2026' ( G.L. /  K.B.) T.D.: 4240' PBTD: N/A Anhydrite Depth: 971'

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole (Stone Corral Formation)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Heavy Mud, Hulls, Cement and Plug according to KCC specifications.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Mr. Rob Long

Phone: (620) 793 - 0915

Address: P.O. BOX 185 City / State: Belpre, KS. 67519

Plugging Contractor: Quality Well Service KCC License #: 31925

Address: 401 West Main, Lyson, KS. 67554 Phone: (620) 727 - 3410  
(Company Name) (Contractor's)


Proposed Date and Hour of Plugging (if known?): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent.

Date: 06/05/2006 Authorized Operator / Agent: Loveness Manje

(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

F.G. Holl Company, LLC  
9431 E. Central, Suite 100  
Wichita, KS 67206

June 28, 2006

Re: BIGGS #1-15  
API 15-185-22771-00-00  
NWNWNW 15-24S-15W, 4950 FSL 4950 FEL  
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely



David P. Williams  
Production Supervisor

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - BIGGS #1  
Located: NW NW NW, Section 15-24S-15W, Stafford County,  
Kansas

OWNER: Northern Lights Oil Company, L.P.  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 13, 1991

COMPLETED: May 19, 1991

TOTAL DEPTH: 4240' Driller T.D.  
4238' Log T.D.

## LOG

## CASING RECORD

0 - 115	Surface Soil and Sand	Spud at 1:30 PM, 5-13-91. Drilled 270' of 12 1/4" hole. Ran 6 joints 8 5/8", 20# new casing. 225.80' pipe set at 268' K.B. Cemented with 165 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 6:45 PM, 5-13-91, by Allied Cementing. Good returns to surface.
115 - 270	Shale	
270 - 971	Shale	
971 - 988	Anhydrite	
988 - 4240'	Lime and Shale	Ran 110 joints used 10.5# casing. 4225.03' pipe set at 4234' K.B. Cemented with 20 bbl. salt flush and 500 gal superflush ahead of 100 sacks Howco Light, followed with 125 sacks F. G. Holl mix. Plug down at 11:45 PM, 5-19-91, by Howco. Shoe joint was 10.30'. Centralizers on Joints 1, 6 and 12. Plugged rathole with 15 sacks.

Deviation Survey: 3/4° at 4111'

RECEIVED  
JUN 07 2006  
KCC WICHITA