

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25538-00-00  
Spot: NENENE Sec/Twnshp/Rge: 9-14S-16W  
330 feet from N Section Line, 80 feet from E Section Line  
Lease Name: SCHECK HAMMERSCHMIDT Well #: 1-9  
County: ELLIS Total Vertical Depth: 3507 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 372  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	222		

\$ 113.98

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/02/2006 1:30 PM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE  
Date/Time Plugging Completed: 07/02/2006 3:30 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3350' w/25 sxs.  
2nd. Plug at 1050' w/25 sxs.  
3rd. Plug at 650' w/100 sxs.  
4th. Plug at 275' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.


Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

  
(TECHNICIAN)

INVOICED  
DATE 7-10-06  
2007060034

RECEIVED

JUL 07 2006

KCC WICHITA

Form CP-2/3

JUL 05 2006

PER