

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00269-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 10-15S-18W
1650 feet from S Section Line, 2310 feet from E Section Line
Lease Name: WASINGER Well #: 1
County: ELLIS Total Vertical Depth: 3595 feet

Operator License No.: 6484
Op Name: ANDERSON ENERGY, INC.
Address: 221 S. BROADWAY, SUITE 302
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3540		
PROD	5.5	3588	2030	150 SX CMT
SURF	8.625	1180	0	550 SX CMT

\$ 116.84

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2006 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 230 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2006 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3310' and topped with 5 sxs cement using a dump bailer.
Cut casing free at 2030'.
Pulled up to 1800' - mixed and pumped 125 sxs cement with 300# hulls.
Pulled up to 1200' - spotted 40 sxs cement with 100# hulls.
Pulled up to 550' - spotted 30 sxs cement with 100# hulls.
Pulled up to 150' and circulated cement with 35 sxs.
POOH. Hole full of cement.

Perfs:

Top	Bot	Thru	Comments
3427	3431		

INVOICED
7-11-2006
200.7060041

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)

RECEIVED

JUL 10 2006

KCC WICHITA

JUL 05 2006

PKT

10-15-18w 34
SW NW SE

FRANCIS OIL & GAS #1 WASSINGER
 Contr. EMPIRE DRILLING ELLIS County
 E 2012 Comm. Comp. 7-3-53 IP 455 BOPD
 PHY POT

Tops	Depth	Datum
ANH	1170	842
HEEB	3250	-1238
TOR	3272	-1260
LANS	3305	-1293
CONG	3583	-1571
ARB	3586	-1574
TD	3595	-1583

Casing
 8" 1180
 5" 3588
 DST 3416-51/45 MIN, 60'
 O & GCM,
 DST 3588-95/1 HR, 2000'
 GAS, 1250' OIL, BHP
 1090#
 DP 3595: 4 BOPH
 LEIKER NORTH POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS